

SURVEY OF ACREAGE PARCEL

QUARTER TOWNSHIP 2, TOWNSHIP 1, RANGE 17

UNITED STATES MILITARY LANDS

CITY OF COLUMBUS, COUNTY OF FRANKLIN, STATE OF OHIO



Legend:

- = MON. FND.
- = 3/4" I.P. FND. UNLESS NOTED
- = I.P. SET
- = MAG. NAIL SET
- ▲ = R.R. SPK. FND.
- ⊙ = PERM. MRKR. SET

I.P. Set are 13/16" I.D. iron pipes 30" long with cap stamped EMHT INC.
Permanent Markers set are one-inch solid iron pins with aluminum cap stamped EMHT INC.

100 0 100 200
GRAPHIC SCALE (in feet)

SURVEY NOTE:
This survey was prepared using documents of record, prior plats of survey, and observed evidence located by an actual field survey.

BASIS OF BEARINGS:
The Bearings shown hereon are based on the Ohio State Plane Coordinate System (South Zone) as per NAD83 (1986 adjustment). Control for bearings was from coordinates of monuments F.C.G.S. 7778 & 8858, having a bearing between them of South 03°57'06" West, established by the Franklin County Engineering Department, using Global Positioning System procedures and equipment.

RECEIVED

MAR 10 2016

Franklin County Engineer
Eugene C. King, P.E., P.S.

By *Heather L. King* 3/9/16
Heather L. King Date
Professional Surveyor No. 8307

 Evans, Mechwart, Hambleton & Tilton, Inc. Engineers • Surveyors • Planners • Scientists 5500 New Albany Road, Columbus, OH 43054 Phone: 614.775.4500 Toll Free: 888.775.3648 emht.com	Date: March 10, 2016	
	Scale: 1" = 100'	
	Job No: 2015-0748	
	Sheet: 1 of 1	
REVISIONS		
MARK	DATE	DESCRIPTION

J:\20150748\DWG\ASSETS\BOUNDARY\20150748-VS-BNDY-06.DWG plotted by WEBB, TEAGLE on 3/10/2016 1:01:58 PM last saved by THEBB on 3/10/2016 1:01:41 PM