

STATE ROAD

In pursuance of an act of the General Assembly of the State of Ohio Entitled an act to lay out and establish a State Road in the Counties of Fairfield, Pickaway and Franklin; Passed March 16, 1840

We the undersigned proceeded on the 18th day of November A. D. 1840 to Survey and establish the Same as the law directs We commenced at a point where the Tarlton Road intersects the Lancaster and Circleville Road in the North line of John Christ home Farm represented by the letter A. from which Point a Walnut Tree 10 inches in diameter bears N 89 W. 30 1/4 links distant it being the Commencing point designated in Said act, we run thence with Said Christ line N 89 W 32 poles to a Stone planted in the line between the Counties of Fairfield and Pickaway, thence with Said line N. 1 E. 1452 poles to a Stone, in Said line South East Corner to the North East Quarter of Section 36. Owned by the Heirs of Jacob Glick, thence N. 3 E. 50 poles to a point in front of said Heirs House 4. poles distant from the Same, thence N. 2 3/4 W. 52 poles to a point 2 poles west of Stephen Bowyers Barn. Thence N. 5 E 30 poles to a point in the County line, thence with the Same N. 1. E. 772 poles to a Red Oak Tree. Thence N. 12 E. 42. poles Crossing a run, thence N. 14 W 30 3/4 poles to a point in Said County line, thence with the Same N. 1 E. 93 poles to a Stake, thence N. 25 E. 32 poles Crossing Halls Mill Race and Big Run to a Stake thence N. 26 W. 27. poles to the North East Corner of Pickaway County thence with the line of Franklin and Fairfield Counties N. 1. E. 402 poles, thence N. 6 3/4 E. 20 poles to a point 2 poles East of the East Row of Fruit Trees in George Bishops Orchard. thence N. 1. E. 58. poles to a point 2 poles East of the North East Corner of his land, Crossing the Lancaster and Columbus Road, thence N. 4 3/4 W. 20 poles to a point in Said County line, thence with the Same N 1 E 140 poles to a Stone the reputed North west Corner of Bloom Township in Fairfield County it being the point of termination recited in the act, and which point we Close the Survey. Mile Trees or Post, were regularly Marked on the line of Road, the whole length of the line of Road as Surveyed is 3253 Poles. Equal to 10 Miles and 53 Poles Between Pickaway and Fairfield Counties 8 Miles an 53 Poles and between Fairfield and Franklin 2 Miles- Given under our hands this---- day of A. D. 1840.

Fees

Commissioners	days each	@ \$1.50	\$13.50
Surveyor	2 days	@ 1.50	3.00
do	3 Platts		12.00
2 Chainmen	2 days each	@ .75	3.00
1 Marker	2 do	.75	1.50

One half the fees to Fairfield County
8/10 of One half to Pickaway and
2/10 of do to Franklin County.

Canal Winchester South Road - from the SE corner of Franklin County to Lithopolis Road
Washington Street - from Lithopolis Road north to the NE corner of Section 1

Victor Reid)
John Chaney) Commissioners
Thomas Elder) -- " --

Per Ohio Road Law of 1831, all State Roads = 60' of ROW

P. N. White Surveyor

010
0010
1840
235